



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600160

Date <u>10/7/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>6-10</u>	Lease <u>Steele</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Parker) #189</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
<u>Surface</u>	<u>8 5/8" (56-24) #</u>	<u>636</u>	
Plug	Bottom of Surface	Fl.	
		<u>680</u>	
Production	Plug Landed @ <u>636</u>	FL	Time On <u>0315</u>
	Pipe Landed @ <u>680</u>	FL	Plug Down <u>0500</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	<u>450</u>	SKS		
Poz. Mix				
Calcium Chloride <u>User ID ZMDL8</u>	2.5	%		
Gel % Flo-Crete <u>1/4 # Per Sack</u>				
Mileage Charge <u>WBSA/CO 2047204</u>	<u>129</u>	Miles		
Fuel Surcharge <u>G/L Acct 800 2090</u>	<u>129</u>	Miles		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>0426-0430</u>		
Disp. Rate <u>5 BPM</u>	Mixing	<u>0430-0449</u>		
Slurry Vol. <u>1.32 Cu. Ft./Sk</u>	Change Valves	<u>0449-0452</u>		
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>0452-0500</u>		
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>63° F</u>				
Total Slurry Vol. <u>105.7</u>	BBLs Cement			
Landed Plug @ <u>300</u>	PSI/Final Lift @ <u>100</u>	PSI		
Pre-Flush W/ <u>20</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>40.4</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>43</u>			
<u>1214/1216</u>		Bulk Truck		<u>43/43</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Kenny & Demetrio

Received By Mr. [Signature]
Customer or His Agent