



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7296 • FAX (970) 353-7712

OUR INVOICE

600037

Date	9-23-11	Well Owner	Kerr McGee	Well No.	18-10	Lease	STEAR
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (PAT-189)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	705		
Surface	8 7/8" CSG-24#	Bottom of Surface		Fl.	700		
Plug		Plug Landed @	655	Fl.	1045		
Production		Pipe Landed @	700	Fl.	1215		

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	440	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack 2049899 DR4				
Mileage Charge 80012690	129	Miles		
Fuel Surcharge	129	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	1130	1135		
Disp. Rate 5 BPM	1135	1201		
Slurry Vol. 1.32 Cu.Ft./Sk	1201	1204		
Slurry Wt. 14.8 - 15.0 PPG	1204	1215		
Water/Cement 6.25 Gal/SK				
Water Temp. 66°F				
Total Slurry Vol. 103.4	BBL'S Cement			
Landed Plug @ 280	PSI/Final Lift @ 260	PSI		
Pre-Flush Wt 30	BBL'S H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace Wt 41.6	BBL'S H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate 5	BBL'S Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202	Pump Truck			43			
1214/1207	Bulk Truck			43/43			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe, Jos II, EVAN, ERNIE

Received By Danny H  
Customer or His Agent