

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400239520

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: Cindy Vue
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832
3. Address: P O BOX 173779 Fax: (720) 929-7832
City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33794-00 6. County: WELD
7. Well Name: STREAR Well Number: 18-10
8. Location: QtrQtr: SENW Section: 10 Township: 2N Range: 67W Meridian: 6
9. Field Name: _____ Field Code: _____

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 12/06/2011 Date of First Production this formation: 12/22/2011
Perforations Top: 7414 Bottom: 7636 No. Holes: 124 Hole size: 0.42

Provide a brief summary of the formation treatment: _____ Open Hole: ☐

NB PERF 7414-7494 HOLES 64 SIZE 0.42 CD PERF 7616-7636 HOLES 60 SIZE 0.38
Frac Niobrara B & C down 4-1/2" Csg w/ 252 gal 15% HCl & 243,768 gal Slickwater w/ 197,250# 40/70, 4,000# SB Excel
Frac Codell down 4-1/2" Csg w/ 196,686 gal Slickwater w/ 149,000# 40/70, 4,000# SB Excel

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 12/23/2011 Hours: 24 Bbls oil: 10 Mcf Gas: 16 Bbls H2O: 0
Calculated 24 hour rate: Bbls oil: 10 Mcf Gas: 16 Bbls H2O: 0 GOR: 1600
Test Method: FLOWING Casing PSI: 1200 Tubing PSI: _____ Choke Size: 12/64
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1334 API Gravity Oil: 49
Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____

Reason for Non-Production: _____

Date formation Abandoned: _____ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt _____

Bridge Plug Depth: _____ Sacks cement on top: _____

Comment: _____

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: _____ Email Cindy.Vue@anadarko.com

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)