



CONSOLIDATED ENERGY
Oil Well Services, LLC

TICKET NUMBER 28220
LOCATION OKla
FOREMAN Tuzz4

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-21-11	9160	Khuai #2	6	10	55w	Lincoln
CUSTOMER Noble Energy - Fullerton Energy						
MAILING ADDRESS						
CITY						
STATE						
ZIP CODE						
			TRUCK #	DRIVER	TRUCK #	DRIVER
			463	Cathy H		
			439	Cecil P		

JOB TYPE SURFACE HOLE SIZE 12 1/4 HOLE DEPTH 320' CASING SIZE & WEIGHT 8 5/8
CASING DEPTH 320' DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 14.7 SLURRY VOL 1.36 WATER gal/sk 4.5 CEMENT LEFT in CASING 30'
DISPLACEMENT 18.4 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting on Monday #25. Rig up & circulate,
mix 265 gals Class 'A' 30 sec 20 gel. Drop plus
and displace 18.4 BBL and shut in.
Cement did circulate approx 6 BBL. to pit

Thanks Tuzz4
crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54013	1	PUMP CHARGE	1025 ⁰⁰	1025 ⁰⁰
5406	100	MILEAGE	5 ⁰⁰	500 ⁰⁰
5407A	12.46	Town Mileage Delivery	15 ⁸	1969 ⁰⁰
11045	265 gals	CLASS 'A'	16 ⁸⁰	4452 ⁰⁰
1102	747 #	Calcium Chloride	1 ⁸⁴	627 ⁴⁸
1118B	498 #	Bentonite	24 ⁰⁰	11952 ⁰⁰
4432	1	8 5/8 wood cup plus	96 ⁰⁰	96 ⁰⁰
		subtotal		8789 ⁰⁰
		less 10% disc.		878 ⁹⁰
				7910.10
		244441	SALES TAX	371.71
			ESTIMATED TOTAL	8281.81

Ravin 9737

AUTHORIZATION Brady Smith TITLE C manager DATE 9/21/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC



TICKET NUMBER 33650
LOCATION Oakley, KS
FOREMAN Walt Dunkel

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

Colorado

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-10-11	9160	Khuai 2	6	10 ^s	55W	Lincoln
CUSTOMER <u>Weipking-Fullerton Energy</u>			TRUCK #			
MAILING ADDRESS			DRIVER			
CITY			TRUCK #			
STATE			DRIVER			
ZIP CODE			TRUCK #			
			DRIVER			

JOB TYPE Prod-O HOLE SIZE 7 7/8 HOLE DEPTH 8000 CASING SIZE & WEIGHT 5 1/2-17#
CASING DEPTH 7752 DRILL PIPE TUBING OTHER RC 4698'
SLURRY WEIGHT 14# SLURRY VOL WATER gal/sk CEMENT LEFT in CASING 34.83'
DISPLACEMENT 179 DISPLACEMENT PSI MIX PSI RATE 6-7 BPM

REMARKS: Safety Meeting, Rig upon Murtin #25, ran Float Equipment
Turb-Centralizers 2-1-3-5-9-10-11-12-14-16-76, Baskets on 2-77
Port Collar on 77, Circ 2 100 Fts and on Bottom. mix 10 sks in Rth, 10 sks
in Mth. Pump 500 gal Mud Flush, mixed 19.5 sks class H, 10% Salt, 5# Kolseal
2% Gel, release Plug & Displace 179-BPM H2O 2 1450# max, handred Plug
2 2000#, released Pressure, Float Held

8:30A

Thank You
Walt & Crew


ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
54018	1	PUMP CHARGE	4050.00	4050.00
5406	100	MILEAGE	5.00	500.00
1115A	215 SKS	Class H Cement	22.00	4,730.00
1111	1028 #	Salt	.42	431.76
1110A	1075 #	Kolseal	.53	569.75
1118B	404 #	Bentonite	.24	96.96
1107	54 #	Flo-Seal	2.66	143.64
11446	500 gal	Mud Flush	1.00	500.00
5407A	10.11	Ton Mileage Delivery	1.58	1,597.00
4159	1	5 1/2 AFD Float Shoe	413.00	413.00
4459	1	5 1/2- Latch down Plug	303.00	303.00
4136	10	5 1/2- Turbo-Centralizers	72.00	720.00
4104	2	Baskets	276.00	552.00
4285	1	Port Collar	2,075.00	2,075.00
				16,682.11
		Less 10% Disc		- 1,668.21
				15,013.90
		244872	SALES TAX	739.56
			ESTIMATED TOTAL	15,753.46

Ravin 3737

AUTHORIZATION Danny Smith TITLE Co Rep DATE 10/10/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 33640

LOCATION Oakley

FOREMAN Kelly Gabe

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-19-11	9160	Kawai #2	6	10 ^s	55 ^w	Lincoln co/c
CUSTOMER Whaipking Fullerton						
MAILING ADDRESS						
CITY		STATE	ZIP CODE			
JOB TYPE						

TRUCK #	DRIVER	TRUCK #	DRIVER
399	Miles S		
566	Cory D		

JOB TYPE <u>Port collar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2</u> <u>12.1</u> #
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8</u>	OTHER _____
SLURRY WEIGHT _____	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT _____	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: Safety Meeting, rigged upon well. Pressured up casing to 1500#
Check Portcollar, opened tool to check for blow. Mixed 250SKs
60/40 Poz5# & 101-seal 1/4" Flt-seal, closed tool, pulled up & reversed out,
washed 80% Acet pumps & lines, rigged down & left location.
Pressure test after closing Tool 2 1500#, Held

Thank you
Kelly & crew

[illegible]

Ravin 3737

5:00 PM
AUTHORIZATION

THE

DATE 10-19-11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.