

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400204903			
PluggingBond SuretyID 20030009			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refilling ☐
Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322
5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
6. Contact Name: SUSAN MILLER Phone: (303)228-4246 Fax: (303)228-4286
Email: smiller@nobleenergyinc.com
7. Well Name: JURGENS Well Number: B16-30D
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 7312

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 8 Twp: 5N Rng: 64W Meridian: 6
Latitude: 40.409950 Longitude: -104.569710

Footage at Surface: 1250 feet FNL/FSL 1442 feet FEL/FWL FEL

11. Field Name: Kersey Field Number: 44600
12. Ground Elevation: 4590 13. County: WELD

14. GPS Data:

Date of Measurement: 08/24/2011 PDOP Reading: 2.1 Instrument Operator's Name: Brian Brinkman

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 75 FEL/FWL 75 Bottom Hole: FNL/FSL 75 FEL/FWL 75
Sec: 8 Twp: 5N Rng: 64W Sec: 8 Twp: 5N Rng: 64W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1309 ft

18. Distance to nearest property line: 1250 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 2010 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	407-87	160	GWA
Niobrara	NBRR	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____
22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian
23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012
23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T5N R64W: Section 8: S/2, S2/N2, S2/NW/4/NE/4; Section 9: All that part of the SW/SW lying West of the county road.

25. Distance to Nearest Mineral Lease Line: 75 ft 26. Total Acres in Lease: 503

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	600	248	600	0
1ST	7+7/8	4+1/2	11.6	0	7,312	587	7,312	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. First string top of cement will be 200' above the Niobrara formation. This is part of a 4-well, multi-well pad which includes the Jurgens PC B08-22D, Jurgens PC B08-23, Jurgens PC B08-24D, Jurgens B16-30D. See 2A doc. no. 400204728 which covers all 4 locations. Unit Configuration: Section 8: SE/SE; Section 9: SW/SW; Section 16: NW/NW; Section 17: NE/NE

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: SUSAN MILLER

Title: Regulatory Analyst II Date: 12/29/2011 Email: smiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 1/20/2012

API NUMBER

05 123 34974 00

Permit Number: _____ Expiration Date: 1/19/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to John Montoya via email at john.montoya@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara. Verify coverage with a cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Operator must meet water well sampling requirements as per Rule 318A.

Attachment Check List

Att Doc Num	Name
2481363	SURFACE CASING CHECK
400204903	FORM 2 SUBMITTED
400204941	30 DAY NOTICE LETTER
400210825	WELL LOCATION PLAT
400210826	DEVIATED DRILLING PLAN
400210838	PROPOSED SPACING UNIT
400210839	PROPOSED SPACING UNIT
400236283	LEGAL/LEASE DESCRIPTION
400236284	PROPOSED SPACING UNIT

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	1/19/2012 9:50:55 AM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) and General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location and will remain in place until the pad reaches final reclamation.
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
General Housekeeping	General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur, prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.

Total: 3 comment(s)