

ad min <admin@overlandresourcesllc.com>

Fwd: Bradbury 12-35

2 messages

Randy Wheat <RVWHEAT@comcast.net>

Mon, Jan 2, 2012 at 2:06 PM

To: Robert Anderson <admin@overlandresourcesllc.com>

Robert,

The 12-35 was plugged with the following specs.

Best regards,

Randy Wheat
4545 S. Monaco St. #116
Denver, CO 80237[720-480-7776](tel:7204807776)
[720-920-9087](tel:7209209087) Fax

From: "James Precup" <James.Precup@state.co.us>
To: "Randy Wheat" <RVWHEAT@comcast.net>
Sent: Friday, December 30, 2011 11:34:21 PM
Subject: RE: Bradbury 12-35

Randy.

Per your verification that you don't have a niobarara play. Then run your drill pipe to 7220 ft pump 75 sks "G" at 15.8 ppg/ WOC tag this plug it should be a minimum of 200 ft above the producing zone. Run your drill pipe to 1400 ft pump 75 sks "G" at 15.8 PPG. Woc tag this plug It needs to be well above 1300 ft. Place 10 sks on surface/ fill mouse hole an rathole with cement to surface. If you think that you have a Niobrara, then run 50 ft below and 200 ft above with a cement plug . If you have any questions, call me in the morning. Thanks, JIM Precup

From: Randy Wheat [<mailto:RVWHEAT@comcast.net>]
Sent: Friday, December 30, 2011 8:41 PM
To: Precup, James
Cc: Gregory Pandolfo

Subject: Bradbury 12-35

Jim,

Can you please provide plugging instructions for this well, or is it 200' above the niobrara as per permit for longstring listed below?

3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage

with cement bond log.

Please advise ASAP as we are going to make decision tonight.

Best regards,

Randy Wheat
4545 S. Monaco St. #116
Denver, CO 80237

720-480-7776
720-920-9087 Fax

Robert Anderson <admin@overlandresourcesllc.com>
To: Randy Wheat <RVWHEAT@comcast.net>

Tue, Jan 3, 2012 at 12:36 PM

Thanks Randy.
Robert
[Quoted text hidden]
