



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600046

Date 9/9/11	Well Owner Kerr McGee	Well No. 1-15 HZ	Lease Price
County Weld	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (X-Home #5)			
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Ft. 915	
Surface 9 5/8" C90-30 # 13 1/2" H4	Bottom of Surface	Ft. 909	
Plug	Plug Landed @	Ft.	Time On 0515
Production	Pipe Landed @	Ft.	Plug Down 0915

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat Type III	680	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Flo-Cete 1/4 # Per Sack	20512041 DEL	
Mileage Charge	96	Miles
Fuel Surcharge	96	Miles
Additional Cement		SKS
Mixing Rate 4 BPM	Pre-Flush	0853 0859
Disp. Rate 5 BPM	Mixing	0859 0929
Slurry Vol. 1.32³ Cu.Ft./Sk	Change Valves	0929 0932
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0932 0945
Water/Cement 6.25 Gal/SK		
Water Temp. 68°F		
Total Slurry Vol. 159.8	BBLs Cement	
Landed Plug @ 900	PSI/Final Lift @ 500	PSI
Pre-Flush W/ 30	BBLs H ₂ O	Tax Reference Code
Displace W/ 67	BBLs H ₂ O	State CO 2.9%
Circulate 6	BBLs Cement	
		Sub Total
		Tax
		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		32			
017/1218		Bulk Truck		32/32			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.