


**From:** [Sutphin, Dirk](#)  
**To:** [Brookshire, Christine](#)  
**Subject:** FW: 05-073-06256\_Form 6 rev. 1 INTENT TO ABANDON\_Mercedes 34-14 1 CBL\_Mountain Petroleum Corp  
**Date:** Wednesday, January 25, 2012 11:16:46 AM

---

Christine,

Please attach this email to the well file. Index as "Correspondence – verbal plugging orders".

Facility Type	Facility ID/ API	Facility Name/ Number	Operator Name/ Number	Status	Field Name/ Number	Location	Related Facilities
<a href="#">WELL</a>	05-073-06256	MERCEDES 32-14 1	MOUNTAIN PETROLEUM CORP 60890	DA	WILDCAT 99999	LINCOLN 073 SWNE 14 15S 52W 6	

Thanks,

Dirk Sutphin  
COGCC, NE Area Engineer  
(303) 894-2100 x 5107

---

**From:** Jake Flora [mailto:jakeflora@kfrcorp.com]  
**Sent:** Sunday, January 15, 2012 1:26 PM  
**To:** Jake Flora; Sutphin, Dirk; Steve Matre; Zane Kuenzler  
**Subject:** 05-073-06256\_Form 6 rev. 1 INTENT TO ABANDON\_Mercedes 34-14 1 CBL\_Mountain Petroleum Corp

All,

Please see attached Rev 1, there was a depth error in the previous form 6 Intent to Abandon.

thanks,

Jake

**Jake Flora**  
Kuenzler & Flora Reserve Corporation  
3310 W. Aqueduct  
Littleton, CO 80123  
720.988.5375  
[www.kfrcorp.com](http://www.kfrcorp.com)

**From:** Jake Flora <jakeflora@kfrcorp.com>  
**To:** "Sutphin, Dirk" <Dirk.Sutphin@state.co.us>; Steve Matre <matresr@qwestoffice.net>; Zane Kuenzler <zaneKuenzler@kfrcorp.com>  
**Sent:** Sunday, January 15, 2012 12:07 PM  
**Subject:** 05-073-06256\_Form 6 INTENT TO ABANDON\_Mercedes 34-14 1 CBL\_Mountain Petroleum Corp

Mr Sutphin,

Please see attached Form 6 intent to abandon for the Mercedes 32-14 #1 in Lincoln Cty. The additional tested intervals are drawn in as theres only room for 2 on the form.

Regards,

**Jake Flora**  
Kuenzler & Flora Reserve Corporation  
3310 W. Aqueduct  
Littleton, CO 80123  
720.988.5375  
[www.kfrcorp.com](http://www.kfrcorp.com)

**From:** "Sutphin, Dirk" <Dirk.Sutphin@state.co.us>  
**To:** Jake.flora <jakeflora@kfrcorp.com>; Zane Kuenzler <zaneKuenzler@kfrcorp.com>; "Quint, Craig" <Craig.Quint@state.co.us>  
**Sent:** Wednesday, January 11, 2012 9:58 AM  
**Subject:** RE: 05-073-06256\_Mercedes 34-14 1 CBL\_Mountain Petroleum Corp

Jake,

This is acceptable. Following the work send a Form 6-Subsequent with the documentation.

Thanks,

Dirk Sutphin  
COGCC, NE Area Engineer  
(303) 894-2100 x 5107

---

**From:** Jake.flora [mailto:jakeflora@kfrcorp.com]  
**Sent:** Wednesday, January 11, 2012 9:32 AM  
**To:** Sutphin, Dirk; Zane Kuenzler; Quint, Craig  
**Subject:** Re: 05-073-06256\_Mercedes 34-14 1 CBL\_Mountain Petroleum Corp

Mr Sutphin,

Per our geologist we squeezed and tested an additional uphole zone prior to abandonment leaving the current wellbore condition as follows:

4857-4861 perfs (Lansing test, unsuccessful)  
4840 CIBP w 2 sx cement  
4700-4701 squeeze perfs  
4666 cement retainer, pumped 75sx below retainer  
CBL TOC @ 4310' (4700'-4310' behind csg)  
4618-4624 perfs (Shawnee test unsuccessful)

Plan Forward:

Set CIBP @ 4600' w 2 sx cement

Proceed w below COGCC PA order:

Contact Craig Quint

1. perfs @ 2500', cmt retainer @ 2400', 40sx
2. 20 sx in csg 1700-1850
3. 20 sx in csg 450-550
4. 10 sx 50-4'
5. Top annulus if open

please advise if acceptable, we plan on plugging tomorrow (Thursday 1/12/2012)

Thanks,

Jake Flora

On Jan 6, 2012, at 3:44 PM, "Sutphin, Dirk" <[Dirk.Sutphin@state.co.us](mailto:Dirk.Sutphin@state.co.us)> wrote:

Jake, Zane,

Thanks for contacting me regarding plugging orders for this well and sending me the CBL. Here are plugging orders as we discussed.

- Plug #1: Perforate and pump 40 sx cement at 4700' with a retainer 100' above perfs.  
Plug #2: Perforate and pump 40 sx cement at 2500' with a retainer 100' above perfs.  
Plug #3: Set 20 sx cement in casing at 1850' – 1700'.  
Plug #4: Set 20 sx cement in casing at 550' – 450'.  
Plug #5: Set 10 sx cement in casing at 50' – 4'. Top up annulus if open.

Turn in a subsequent report when done. Include job tickets for all plugs and a wellbore diagram.

Sincerely,

Dirk Sutphin  
COGCC, NE Area Engineer  
(303) 894-2100 x 5107

---

**From:** Jake Flora [mailto:jakeflora@kfrcorp.com]  
**Sent:** Friday, January 06, 2012 1:34 PM  
**To:** Sutphin, Dirk; Zane Kuenzler  
**Subject:** 05-073-06256\_Mercedes 34-14 1 CBL\_Mountain Petroleum Corp

Dirk,

For PA request please see attached bond log for the following well;

Mercedes 32-14 1  
15s 52w 14  
Lincoln Cty, CO

Zane is in the field with limited computer access-

Thanks,

Jake

**Jake Flora**  
Kuenzler & Flora Reserve Corporation  
3310 W. Aqueduct  
Littleton, CO 80123  
720.988.5375  
[www.kfrcorp.com](http://www.kfrcorp.com)