

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400233707

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-34529-00

6. County: WELD

7. Well Name: THOMASON

Well Number: 25-16R

8. Location: QtrQtr: NESW Section: 16 Township: 2N Range: 65W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL

Status: PRODUCING

Treatment Date: 11/03/2011

Date of First Production this formation: 11/29/2011

Perforations	Top:	7126	Bottom:	7367	No. Holes:	124	Hole size:	0.42
--------------	------	------	---------	------	------------	-----	------------	------

Provide a brief summary of the formation treatment:

Open Hole:

NB PERF 7126-7266 HOLES 60 SIZE 0.42 CD PERF 7351-7367 HOLES 64 SIZE 0.38
Frac Niobrara B & C down 4-1/2" Csg w/ 252 gal 15% HCl & 239,568 gal Slickwater w/ 201,820# 40/70, 4,000# SuperLC
Frac Codell down 4-1/2" Csg w/ 202,986 gal Slickwater w/ 150,560# 40/70, 4,000# SuperLC

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date:	11/30/2011	Hours:	24	Bbls oil:	10	Mcf Gas:	100	Bbls H2O:	0
-------	------------	--------	----	-----------	----	----------	-----	-----------	---

Calculated 24 hour rate:	Bbls oil:	10	Mcf Gas:	100	Bbls H2O:	0	GOR:	10000
--------------------------	-----------	----	----------	-----	-----------	---	------	-------

Test Method: FLOWING	Casing PSI: 1525	Tubing PSI:	Choke Size: 12/64
----------------------	------------------	-------------	-------------------

Gas Disposition:	SOLD	Gas Type:	WET	BTU Gas:	1251	API Gravity Oil:	49
------------------	------	-----------	-----	----------	------	------------------	----

Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: ☐ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: _____ Sacks cement on top: _____

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: 12/19/2011 Email: Cindy.Vue@anadarko.com

Attachment Check List

Att Doc Num	Name
400233707	FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)