



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600155

Date 10-9-11	Well Owner Kerr McGee	Well No. 22-9	Lease JOLLAISTOWN FARMS
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (XTREME-11)			
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Fl.	
Surface	8 7/8" CSG-244	642	
	Bottom of Surface	Fl.	
		637	
Plug	Plug Landed @ 593	Fl.	Time On 2230
Production	Pipe Landed @ 637	Fl.	Plug Down 0136

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	400	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	114	Miles		
Fuel Surcharge	114	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0050-0055	
Disp. Rate	5 BPM	Mixing	0055-0119	
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	0119-0122	
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0122-0136	
Water/Cement	6.25 Gal/SK			
Water Temp.	48°F			
Total Slurry Vol.	94.0	BBLs Cement		
Landed Plug @	250	PSI/Final Lift @ 236	PSI	
Pre-Flush Wt	20	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace Wt	37.7	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		38			
1217		Bulk Truck		38/38			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, SIM, ADAM, CHRIS**

Received By **[Signature]**

Customer or Representative