

FORM  
2Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐Refiling ☐Sidetrack ☐

Document Number:

400246195

PluggingBond SuretyID

20090067

3. Name of Operator: WIEPKING-FULLERTON ENERGY LLC4. COGCC Operator Number: 963405. Address: 4600 S DOWNING STCity: ENGLEWOOD State: CO Zip: 801136. Contact Name: Jack Fincham Phone: (303)906-3335 Fax: (303)761-9067  
Email: fincham4@msn.com7. Well Name: Napali Well Number: # 8

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 8400

## WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 17 Twp: 10S Rng: 55W Meridian: 6Latitude: 39.180470 Longitude: -103.577570Footage at Surface: 1980 feet FNL/FSL 1980 feet FEL/FWL FWL11. Field Name: Great Plains Field Number: 3275612. Ground Elevation: 5180.32 13. County: LINCOLN

## 14. GPS Data:

Date of Measurement: 01/12/2012 PDOP Reading: 2.6 Instrument Operator's Name: Keith Westfall15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 1980 ft18. Distance to nearest property line: 1980 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1322 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Atoka	ATOK			
Cherokee	CHRK			
Keyes	KEYES			
Lansing	LNSNG			
Marmaton	MRTN			
Morrow	MRRW			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
All, Sec. 17, T10S, R55W

25. Distance to Nearest Mineral Lease Line: 1980 ft 26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☒ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: No mud or water pits.

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	300	250	300	0
1ST	7+7/8	5+1/2	17	0	8,400	300	8,400	6,500

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments No Conductor casing will be used. No mud or water pits. Closed loop system will be used during drilling operations.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jack Fincham

Title: Agent Date: \_\_\_\_\_ Email: fincham4@msn.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**API NUMBER**

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**CONDITIONS OF APPROVAL, IF ANY:**

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

**Attachment Check List**

Att Doc Num	Name
400246209	LOCATION DRAWING
400246215	30 DAY NOTICE LETTER
400246218	OTHER
400246220	TOPO MAP
400246221	SURFACE AGRMT/SURETY
400246485	PROPOSED BMPs

Total Attach: 6 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>

Total: 0 comment(s)

## **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>
Storm Water/Erosion Control	<p>BMP Plan</p> <p>Wiepking-Fullerton Energy, L.L.C. 4600 S. Downing St. Englewood, CO 80113 303-789-1798 303-761-9067 (fax)</p> <p>Certification to Discharge Under CDPS General Permit COR-03000 Stormwater Discharges Associated with Construction</p> <p>Certification Number COR 39788</p> <p>Napali # 8 well T10S, R55W Sec. 17: SE1/4NW1/4 Lincoln County, Colorado</p> <p>Description of Well Site and Construction Area 1-3 acre site with access road for drilling of oil and gas well. Terrain is flat with native grass and sagebrush. Surface Roughening will be used on low side of drill site to reduce speed of runoff, increase infiltration, reduce erosion, trap sediment and prepare soil for reseeding. A dirt berm will be placed on the North, East and South edge of the well pad to protect surface water located 1000' Northwest of well pad. No Water or Mud pits will be excavated. A closed loop system will be used for all Water and Drilling Mud. Topsoil will be separated and spread on drill site as final operation before reseeding operations, which will be completed within 6 months weather permitting. After drilling operations are completed and to prevent soil erosion. The drill site will be disked and straw crimped in or manure spread.</p> <p>Stormwater Management Plan (SWMP) is on file in Wiepking-Fullerton Energy, L.L.C. office.</p> <p>Spill Prevention, Control and Countermeasure Plan is on file in Wiepking-Fullerton Energy, L.L.C. office.</p>

Total: 1 comment(s)