

BMP Plan

Wiepking-Fullerton Energy, L.L.C.
4600 S. Downing St.
Englewood, CO 80113
303-789-1798
303-761-9067 (fax)

Certification to Discharge
Under
CDPS General Permit COR-03000
Stormwater Discharges Associated with Construction

Certification Number COR 39788

Napali # 8 well
T10S, R55W
Sec. 17: SE1/4NW1/4
Lincoln County, Colorado

Description of Well Site and Construction Area

1-3 acre site with access road for drilling of oil and gas well. Terrain is flat with native grass and sagebrush. Surface Roughening will be used on low side of drill site to reduce speed of runoff, increase infiltration, reduce erosion, trap sediment and prepare soil for reseeding. A dirt berm will be placed on the North, East and South edge of the well pad to protect surface water located 1000' Northwest of well pad. No Water or Mud pits will be excavated. A closed loop system will be used for all Water and Drilling Mud. Topsoil will be separated and spread on drill site as final operation before reseeding operations, which will be completed within 6 months weather permitting. After drilling operations are completed and to prevent soil erosion. The drill site will be disked and straw crimped in or manure spread.

Stormwater Management Plan (SWMP) is on file in Wiepking-Fullerton Energy, L.L.C. office.

Spill Prevention, Control and Countermeasure Plan is on file in Wiepking-Fullerton Energy, L.L.C. office.