



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600167

Date <u>10/17/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>26-32</u>	Lease <u>Howard</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>1265</u>	
<u>Surface</u> <u>8 5/8" 156-24"</u>	Bottom of Surface	Ft. <u>1252</u>	
Plug	Plug Landed @ <u>1208</u>	Fl. Time On <u>2140</u>	
Production	Pipe Landed @ <u>1252</u>	Fl. Plug Down <u>0200</u>	

Description	Qty	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III 100% Express</u>	790	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	216	Miles		
Fuel Surcharge	216	Miles		
Additional Cement	40	SKS		
Mixing Rate 4 BPM	Pre-Flush	0102-	0108	
Disp. Rate 5 BPM	Mixing	0108-	0142	
Slurry Vol. 1.32 Cu. Ft./Sk	Change Valves	0142-	0145	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0145-	0200	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>52° F</u>				
Total Slurry Vol. <u>195.1</u>	BBLS Cement			
Landed Plug @ <u>800</u>	PSI/Final Lift @ <u>400</u>	PSI		
Pre-Flush Wt. <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace Wt. <u>74.8</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>72</u>			
<u>1211/1210</u>		Bulk Truck		<u>72/72</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Kenny Demetrio

Received By Dany H
Customer or His Agent