

Map Unit Description

Weld County, Colorado, Southern Part

79 Weld loam, 1 to 3 percent slopes

Setting

Elevation: 4850 to 5000 feet
Mean annual precipitation: 13 to 17 inches
Mean annual air temperature: 48 to 55 degrees F
Frost-free period: 100 to 155 days

Composition

Weld and similar soils: 80 percent
Minor components: 20 percent

Description of Weld

Setting

Landform: Plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Eolian deposits

Properties and Qualities

Slope: 1 to 3 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately low or moderately high (0.06 to 0.20 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 6 percent
Gypsum maximum: 0 percent
Available water capacity: High (about 10.2 inches)

Interpretive Groups

Land capability classification (irrigated): 2e
Land capability (non irrigated): 3e
Ecological site: Loamy Plains (R067BY002CO)

Typical Profile

0 to 8 inches: loam
8 to 15 inches: clay
15 to 60 inches: silt loam
60 to 64 inches: silt loam

Minor Components

Keith

Percent of map unit: 7 percent

Wiley

Percent of map unit: 7 percent

Adena

Percent of map unit: 6 percent