

Well	: IONE 6-0-10	
Field	: WATTENBERG	
County	: WELD COUNTY	State : Colorado
Surface	: 1044' FNL, 958' FEL, NENE Sec 10-T2N-R66W	
	:	
	:	
Grd Elev	: 5006' GR	KB Elev : 5018' KB

KB Elev : 5018' KB

Sussex	4692'
Niobrara	7363'
Codell	7635'
J Sand	8087'

Spud	09-21-11
TD	09-26-11

8-5/8", Set @ 1003'
Cemented with 370 sxs

4-1/2" production casing set @ 8212'
Cemented with 610 sx

Set @ 7360'. 01-17-12
Drilled out on 01-18-12

Perf'd the Niobrara 7409' - 7438' @ 4 spf
Frac'd the Niobrara 7409' - 7438' (156 holes), w/ 131,838 gals 18 #
Vistar Hybrid cross linked gel containing 250,060 # 20/40 sand.
10-17-11

Set @ 7600'. 10-18-11
Drilled out on 01-18-12

Perf'd the Codell 7635' - 7656' @ 2 spf
Frac'd the Codell 7635' - 7656' (42holes) w/ 108,339 gal 22
Vistar Hybrid cross linked gel containing 250,300 # 20/40
sand. 10-17-11

Set @ 7750'. 10-17-11
Drilled out on 01-18-12

Perf'd the J Sand from 8121' - 8148' @ 2 spf
Frac'd the J-Sand 8121'-8148', (54 holes)w/ 165,270 gal 18 #
Vistar Hybrid cross linked gel containing 250,360 # 20/40 Sand.
10-17-11

2-3/8". Set @ 8115.71'

TD 8225'

Sheilla Reed-High

--	--	--	--