



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600181

Date 10/13/2011	Well Owner Kerr McGee	Well No. 11-9	Lease JOHNSTOWN FARM
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700	(XTREME #11)		
City, State Zip Denver, Colorado 80202			
Type of Job 555	Depth 638	Ft. 638	
Surface 8 5/8" CSG 24"	Bottom of Surface 633	Ft. 633	
Plug	Plug Landed @ 589	Ft. 589	Time On 2330
Production	Ripe Landed @ 633	Ft. 633	Plug Down 0300

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	400	SKS		
Poz. Mix				
Calcium Chloride 2048806 DRT	25	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge 800/12090	114	Miles		
Fuel Surcharge	114	miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush 0223	0226		
Disp. Rate 5 BPM	Mixing 0226	0250		
Slurry Vol. 1.32³ Cu.Ft./Sk	Change Valves 0250	0253		
Slurry Wt. 14.8 - 15.0 PPG	Displacement 0253	0300		
Water/Cement 6.25 Gal/SK				
Water Temp. 56				
Total Slurry Vol. 94.0	BBLs Cement			
Landed Plug @ 400	PSI/Final Lift @ 700	PSI		
Pre-Flush Wt 15	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace Wt 37.4	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		38			
1218/1214		Bulk Truck		35/35			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jim/Adam/Chris**

Received By **Tom Bower**
Customer or His Agent