



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600175

Date <u>10-28-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>13-9</u>	Lease <u>JOLINSTOWN FARMS</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme II)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL <u>643</u>	
<input checked="" type="checkbox"/> Surface <u>8 3/8" CSG-24H</u>	Bottom of Surface	FL <u>638</u>	
Plug	Plug Landed @ <u>572</u>	FL	Time On <u>1800</u>
Production	Pipe Landed @ <u>638</u>	FL	Plug Down <u>2000</u>

Description	Qty.	Meas.	Unit Price.	Amount
Set Up Charge	1			
Cement Neat	400	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	80	Miles		
Fuel Surcharge	80	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1920 - 1925		
Disp. Rate 5 BPM	Mixing	1925 - 1949		
Slurry Vol. 1.32' Cu.Ft./Sk	Change Valves	1949 - 1952		
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1952 - 2000		2048851
Water/Cement 6.25 Gal/SK				
Water Temp. <u>38°F</u>				200 2040 DPK
Total Slurry Vol. <u>94.0</u>	BBLs Cement			
Landed Plug @ <u>220</u>	PSI/Final Lift @ <u>200</u>	PSI		
Pre-Flush W/ <u>20</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>37.6</u>	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate <u>5</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1202</u>		Pump Truck		<u>40</u>			
<u>1218</u>		Bulk Truck		<u>40</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe Joshi, Evan, Eric

Received By [Signature]
Customer or His Agent