



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600188

Date <b>11-3-11</b>	Well Owner <b>Kerr McGee</b>	Well No. <b>19-9</b>	Lease <b>Johnstown Farms</b>
County <b>Weld</b>	State <b>Colorado</b>		
Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b>			
Address <b>1999 Broadway, Suite 3700</b>	<b>(Xtreme II)</b>		
City, State Zip <b>Denver, Colorado 80202</b>			
Type of Job	Depth	Fl.	
<b>Surface</b>	<b>8 5/8 CSG #24</b>	<b>643</b>	
	Bottom of Surface	Fl.	
		<b>639</b>	
Plug	Plug Landed @ <b>595</b>	Fl.	Time On <b>0400</b>
	Pipe Landed @ <b>639</b>	Fl.	Plug Down <b>0915</b>
Production			

Description	Qty	Meas	Unit Price	Amount
Set Up Charge	1			
Cement Neat <b>TYPE III</b>	<b>400</b>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	<b>114</b>	Miles		
Fuel Surcharge	<b>114</b>			
Additional Cement		SKS		
Mixing Rate <b>4 BPM</b>	Pre-Flush	<b>0837</b>	<b>0840</b>	
Disp. Rate <b>5 BPM</b>	Mixing	<b>0840</b>	<b>0904</b>	
Slurry Vol. <b>1.32 Cu.Ft./Sk</b>	Change Valves	<b>0904</b>	<b>0907</b>	
Slurry Wt. <b>14.8 - 15.0 PPG</b>	Displacement	<b>0907</b>	<b>0915</b>	<b>2048816</b>
Water/Cement <b>6.25 Gal/SK</b>				<b>800 2090 125</b>
Water Temp. <b>61°F</b>				
Total Slurry Vol. <b>94.0</b>	BBLs Cement			
Landed Plug @ <b>200</b>	PSI/Final Lift @ <b>175</b>	PSI		
Pre-Flush Wt. <b>15</b>	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace Wt. <b>37.5</b>	BBLs H <sub>2</sub> O	State <b>CO 2.9%</b>	Tax	
Circulate <b>5</b>	BBLs Cement	<b>600188</b>	Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1201</b>		Pump Truck		<b>38</b>			
<b>1216/1218</b>		Bulk Truck		<b>38/38</b>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jim, Adam, Chris, James**

Received By **[Signature]**  
Customer or His Agent