



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600196

Date <u>10/31/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>35-9</u>	Lease <u>THUS BAY FATS</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (XTREME# 11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>642</u>	
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Fl. <u>637</u>	
Plug	Plug Landed @ <u>593</u>	Fl. Time On <u>1200</u>	
Production	Pipe Landed @ <u>637</u>	Fl. Plug Down <u>1345</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>400</u>	SKS		
Poz. Mix				
Calcium Chloride	<u>2.5</u>	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	<u>114</u>	Miles		
Fuel Surcharge	<u>114</u>	miles		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>1309</u>	<u>1312</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>1312</u>	<u>1335</u>	
Slurry Vol. <u>1.32 Cu. Ft./Sk</u>	Change Valves	<u>1335</u>	<u>1339</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>1338</u>	<u>1345</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>51</u>				
Total Slurry Vol. <u>94.0</u>	BBLs Cement			
Landed Plug @ <u>350</u>	PSI/Final Lift @ <u>125</u>	PSI		
Pre-Flush Wt <u>20</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace Wt <u>37.7</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>38</u>			
<u>1214/1219</u>		Bulk Truck		<u>38/38</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM ADAM/CHRIS JAMES

Received By [Signature]
Customer or His Agent