



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600254

Date <u>12/20/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>27-14</u>	Lease <u>River Bend</u>
County <u>weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>955</u>	
<u>(Surface)</u> <u>8 5/8" CSG-24 #</u>	Bottom of Surface	Ft. <u>950</u>	
Plug	Plug Landed @ <u>906</u>	Ft.	Time On <u>2000</u>
Production	Pipe Landed @ <u>950</u>	Ft.	Plug Down <u>0130</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	<u>1000</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete <u>1/4</u> # Per Sack				
Mileage Charge	<u>198</u>	Miles		
Fuel Surcharge	<u>198</u>	Miles		
Additional Cement		SKS		
Mixing Rate <u>4</u> BPM	Pre-Flush	<u>0044</u>	<u>0050</u>	
Disp. Rate <u>5</u> BPM	Mixing	<u>0050-</u>	<u>0116</u>	
Slurry Vol. <u>1.32</u> Cu.Fl./Sk	Change Valves	<u>0116-</u>	<u>0119</u>	
Slurry Wt. <u>14.8 - 15.0</u> PPG	Displacement	<u>0119-</u>	<u>0130</u>	
Water/Cement <u>6.25</u> Gal/SK				
Water Temp. <u>67</u> °F				
Total Slurry Vol. <u>141</u>	BBLS Cement			
Landed Plug @ <u>500</u>	PSI/Final Lift @ <u>200</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>57.6</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>106</u>	<u>Duaine Bell</u>		
<u>1217/1218</u>		Bulk Truck		<u>106/106</u>	<u>User ID ZDSB4</u>		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Kenny, Demetrio & Steve

Received By

WBS/NO/CC 2045301, DRL

G/L Acct. 80012090

[Signature]
Customer or His Agent