

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
All, Sec. 29, T10S, R55W

25. Distance to Nearest Mineral Lease Line: 1980 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: Land Farming Land Spreading Disposal Facility Other: Backfill when dry

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	300	250	300	0
1ST	7+7/8	5+1/2	17	0	8,400	300	8,400	6,500

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments No Conductor casing will be used

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Jack Fincham

Title: Agent Date: _____ Email: fincham4@msn.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER Permit Number: _____ Expiration Date: _____

05

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400249440	30 DAY NOTICE LETTER
400249441	LOCATION DRAWING
400249442	TOPO MAP
400249443	PROPOSED BMPs
400249445	OTHER

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Storm Water/Erosion Control	<p>BMP Plan</p> <p>Wiepking-Fullerton Energy, L.L.C. 4600 S. Downing St. Englewood, CO 80113 303-789-1798 303-761-9067 (fax)</p> <p>Certification to Discharge Under CDPS General Permit COR-03000 Stormwater Discharges Associated with Construction</p> <p>Certification Number COR 39788</p> <p>Mahalo # 8 well T10S, R55W Sec. 29: NE1/4SW1/4 Lincoln County, Colorado</p> <p>Description of Well Site and Construction Area 1-3 acre site with access road for drilling of oil and gas well. Terrain is flat with native grass and sagebrush. No receiving waters will be affected by well pad. Surface Roughening will be used on low side of drill site to reduce speed of runoff, increase infiltration, reduce erosion, trap sediment and prepare soil for reseeding. Mud and Water Pits will be reclaimed within 3 months weather permitting. Topsoil will be separated and spread on drill site as final operation before reseeding operations within 6 months weather permitting. To prevent soil erosion site will be disked and straw crimped in or manure spread.</p> <p>Stormwater Management Plan (SWMP) is on file in Wiepking-Fullerton Energy, L.L.C. office.</p> <p>Spill Prevention, Control and Countermeasure Plan is on file in Wiepking-Fullerton Energy, L.L.C. office.</p>

Total: 1 comment(s)