



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600163

Date <u>10/9/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>280-23 H2</u>	Lease <u>Powers</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #6)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>957</u>	
<u>Surface</u> <u>9 5/8" 158-36# 13 1/2 Hole</u>	Bottom of Surface	Ft. <u>946</u>	
Plug	Plug Landed @ <u>902</u>	Ft. <u>Time On 1510</u>	
Production	Pipe Landed @ <u>946</u>	Ft. <u>Plug Down 2100</u>	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat <u>✓ Type III 100% Excess</u>	760	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Fio-Cete <u>1/4</u> # Per Sack		
Mileage Charge <u>2056994 DRL</u>	198	Miles
Fuel Surcharge <u>800.12090</u>	198	Miles
Additional Cement	40	SKS
Mixing Rate 4 BPM	Pre-Flush 2006-	2012
Disp. Rate 5 BPM	Mixing 2012-	2043
Slurry Vol. 1.32 Cu.Ft./Sk	Change Valves 2043-	2046
Slurry Wt. 14.8 - 15.0 PPG	Displacement 2046-	2100
Water/Cement 6.25 Gal/SK		
Water Temp <u>58°F</u>		
Total Slurry Vol. <u>174</u>	BBLs Cement	
Landed Plug @ <u>800</u>	PSI/Final Lift @ <u>400</u>	PSI
Pre-Flush W/ <u>30</u>	BBLs H ₂ O	Tax Reference Code
Displace W/ <u>69.7</u>	BBLs H ₂ O	State <u>CO 2.9%</u>
Circulate <u>7</u>	BBLs Cement	Sub Total
		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>166</u>			
<u>1214/1218</u>		Bulk Truck		<u>169/166</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.