



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199681

Date 6/19/2011	Well Owner Kerr McGee	Well No. 26-32	Lease FEHRN
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700	(XTREME #1)		
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Fl. 919	
Surface 8 5/8" CSG 24"	Bottom of Surface	Fl. 909	
Plug	Plug Landed @ 867	Fl. 909	Time On 0800
Production	Pipe Landed @ 909	Fl. 909	Plug Down 1000

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	570	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge 2052748 DTL	186	Miles		
Fuel Surcharge 56012090	186	miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	0914	0920	
Disp. Rate 5 BPM	Mixing	0920	0946	
Slurry Vol. 1.32³ Cu.Ft./Sk	Change Valves	0946	0949	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0949	1000	
Water/Cement 6.25 Gal/SK				
Water Temp. 52				
Total Slurry Vol. 134	BBLS Cement			
Landed Plug @ 380	PSI/Final Lift @ 200	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 55	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		62			62
1214/1215		Bulk Truck		62/42			62/42

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JIM/ADAM/STEVE/KRIS/KENNY**

Received By **[Signature]**

Customer or His Agent