

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400229715

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 10347 4. Contact Name: Christi Scritchfield
2. Name of Operator: CONTINENTAL RESOURCES INC Phone: (580) 233-8955
3. Address: PO BOX 1032 Fax: (580) 548-5293
City: ENID State: OK Zip: 73703

5. API Number 05-123-34199-00 6. County: WELD
7. Well Name: Hahn Well Number: 1-4H
8. Location: QtrQtr: SESE Section: 4 Township: 7N Range: 62W Meridian: 6
9. Field Name: KEOTA Field Code: 44350

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING

Treatment Date: 12/02/2011 Date of First Production this formation: 12/15/2011

Perforations Top: 7064 Bottom: 10554 No. Holes: Hole size:

Provide a brief summary of the formation treatment: Open Hole: ☒

Pumped 18 stage frac job via sliding sleeves. Average rate was 51.5 bpm. Max rate was 59 bpm. Average pressure was 3926 psi. Max pressure was 8687 psi.

Totals: Water - 46,995 bbls; 40/70 sand - 185,860 lbs; 20/40 sand - 2,588,020 lbs; 20/40 Resin - 565,480 lbs.

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 01/08/2012 Hours: 24 Bbls oil: 68 Mcf Gas: 211 Bbls H2O: 167

Calculated 24 hour rate: Bbls oil: 68 Mcf Gas: 211 Bbls H2O: 167 GOR: 3103

Test Method: Production Casing PSI: 200 Tubing PSI: 2500 Choke Size: 46

Gas Disposition: FLARED Gas Type: WET BTU Gas: 0 API Gravity Oil: 37

Tubing Size: 2 + 7/8 Tubing Setting Depth: 10456 Tbg setting date: 12/04/2011 Packer Depth: 10456

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

The Gas BTU is 0 because the gas analysis won't be ran until the gas pipeline is connected. A sundry will be submitted with this information as soon as it is done.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Christi

Title: Scritchfield Date: Email christiscritchfield@contres.com

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)