



# Gulfport Energy Corporation Downhole Schematic

PROPOSED  
WELLBORE

WELL NAME: MOFFAT 22-11-1 ST1	FIELD: Craig (13500)	API: 05-081-07669
SURFACE LOCATION: 1891' FNL & 1699' FWL (SENW) Sec 11 - T6N - R91W Moffat County, CO		
ELEVATIONS: KB - CHF 14.6' KB 6256.0' DF 6255.0' GL 6241.0'	LAT: 40.494343 LONG: -107.575764	
B. Osborn 11/05/2011	SPUD DATE: 09/30/2011	

CASING and TUBING INFORMATION					
SIZE	WEIGHT	GRADE	THREAD	DEPTH	HOLE
9 <sup>5</sup> / <sub>8</sub> "	36#	J-55	ST&C	0' - 885'	12 <sup>1</sup> / <sub>4</sub> "
7"	23#	J-55	LT&C	0' - 6310'	8 <sup>3</sup> / <sub>4</sub> "
4 <sup>1</sup> / <sub>2</sub> "	9.5#	J-55	LT&C	6050' - 7870'	6 <sup>1</sup> / <sub>8</sub> "

16" Drive pipe @ 65'  
9<sup>5</sup>/<sub>8</sub>" csg @ 885' kb. Cmt'd w/ 209 sxs prem lite & 100 sxs Type 3.

TOC @ 1680' (CBL)

4<sup>1</sup>/<sub>2</sub>" Liner Top @ 6050'

Window @ 6119' - 6134'

CIBP  
6134'

7" csg @ 6310'.  
Cmt'd w/ 302 sxs prem lite  
& 150 sxs class G

TD @ 7870' MD

4<sup>1</sup>/<sub>2</sub>" Liner @ 7870'