



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199751

Date <u>7/12/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>7-32</u>	Lease <u>FEHRD</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700</u>	<u>(XTREME #6)</u>		
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL	<u>917</u>
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	FL	<u>907</u>
Plug	Plug Landed @ <u>863</u>	FL	Time On <u>0900</u>
Production	Pipe Landed @ <u>907</u>	FL	Plug Down <u>1120</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>570</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack	<u>2052726 DRL</u>			
Mileage Charge	<u>186</u>	Miles		
Fuel Surcharge	<u>186</u>	MILES		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>1035</u>	<u>1041</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>1041</u>	<u>1106</u>	
Slurry Vol. <u>1.32" Cu. Ft./Sk</u>	Change Valves	<u>1106</u>	<u>1109</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>1109</u>	<u>1120</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>60</u>				
Total Slurry Vol. <u>134</u>	BBLS Cement			
Landed Plug @ <u>375</u>	PSI/Final Lift @ <u>125</u>	PSI		
Pre-Flush W/ <u>3D</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>54.5</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>62</u>			
<u>1207/1217</u>		Bulk Truck		<u>42/62</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/STEVE/CRIS

Received By [Signature]

Customer or His Agent