



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199684

Date	6/23/11	Well Owner	Kerr McGee	Well No.	8-32	Lease	FEHAN
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme 6)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	914		
Surface	8 5/8 CSG #24	Bottom of Surface		Ft.	904		
Plug		Plug Landed @	864	Ft.	Time On	0900	
Production		Pipe Landed @	904	Ft.	Plug Down	1130	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat Type III 100% Excess	570	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	2052727 Del	204	Miles	
Fuel Surcharge	800/2090	204	miles	
Additional Cement	60	SKS		
Mixing Rate	4 BPM	Pre-Flush	1036	1040
Disp. Rate	5 BPM	Mixing	1040	1115
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves	1115	1118
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1118	1130
Water/Cement	6.25 Gal/SK			
Water Temp.	64°F			
Total Slurry Vol.	148.1	BBLS Cement		
Landed Plug @	375	PSI/Final Lift @	150	PSI
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	55	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	4	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		68			
1214/1218		Bulk Truck		68/68			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Steve, Kenny, Chris

Received By *Mari Vackward*
Customer or His Agent