



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80683 • (970) 353-1299 • FAX (970) 353-7712

OUR INVOICE

600161

Date <u>10/8/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>24-32</u>	Lease <u>Howard</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #15)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL <u>1236</u>	
(Surface)	Bottom of Surface	FL <u>1226</u>	
Plug	Plug Landed @ <u>1182</u>	FL	Time On <u>1715</u>
Production	Pipe Landed @ <u>1226</u>	FL	Plug Down <u>2000</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III 100% Excess</u>	770	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge <u>505760 DRE</u>	216	Miles		
Fuel Surcharge <u>8007296</u>	216	Miles		
Additional Cement	40	SKS		
Mixing Rate 4 BPM	Pre-Flush	1903-	1909	
Disp. Rate 5 BPM	Mixing	1909-	1943	
Slurry Vol. 1.32 Cu.Ft./Sk	Change Valves	1943-	1946	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1946-	2000	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>57°F</u>				
Total Slurry Vol. <u>190.4</u>	BBLS Cement			
Landed Plug @ <u>900</u>	PSI/Final Lift @ <u>450</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>75.1</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>6</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>72</u>			
<u>1217/1218</u>		Bulk Truck		<u>72/72</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Kenny's Demaleio

Received By John Salame
Customer or His Agent