



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600180

Date <u>10/12/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>41-32</u>	Lease <u>HOWARD</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700</u>	<u>(XTREME #15)</u>		
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth <u>1281</u>		
Surface <u>8 5/8 CS&24"</u>	Bottom of Surface <u>1260</u>		
Plug	Plug Landed @ <u>1216</u>	Time On <u>1830</u>	
Production	Pipe Landed @ <u>1260</u>	Plug Down <u>0500</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>790</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	<u>216</u>	Miles		
Fuel Surcharge	<u>216</u>	MILES		
Additional Cement	<u>40</u>	SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>0350</u>	<u>0356</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>0356</u>	<u>0442</u>	
Slurry Vol. <u>1.32 Cu. Ft./Sk</u>	Change Valves	<u>0442</u>	<u>0445</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>0445</u>	<u>0500</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>54</u>				
Total Slurry Vol. <u>195.1</u>	BBLS Cement			
Landed Plug @ <u>980</u>	PSI/Final Lift @ <u>375</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>77.3</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>	Pump Truck			<u>72</u>			
<u>2011219</u>	Bulk Truck			<u>72/72</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/Chris

Received By

2057792.DRL
80012090
Frank Worlan