

## Kubeczko, Dave

---

**From:** Kubeczko, Dave  
**Sent:** Wednesday, February 15, 2012 12:11 PM  
**To:** Kubeczko, Dave  
**Subject:** FW: EnCana Oil & Gas (USA), Albertson G15 7101 Pad, Lot 7 Sec 15 T7S R101W, Garfield County, Form 2A (#400245174) Review

**Categories:** Orange - Operator Correspondence

Scan No 2034142      CORRESPONDENCE      2A#400245174

---

**From:** Mitchell, Heather R. [<mailto:Heather.Mitchell@encana.com>]  
**Sent:** Monday, January 30, 2012 1:26 PM  
**To:** Kubeczko, Dave  
**Subject:** RE: EnCana Oil & Gas (USA), Albertson G15 7101 Pad, Lot 7 Sec 15 T7S R101W, Garfield County, Form 2A (#400245174) Review

Thank you Dave - Encana agrees to these COAs.

Heather Mitchell  
Regulatory Analyst  
Encana Oil & Gas (USA) Inc.  
720-876-3070 Office  
720-375-4879 Cell  
720-876-4070 Fax  
[heather.mitchell@encana.com](mailto:heather.mitchell@encana.com)

---

**From:** Kubeczko, Dave [<mailto:Dave.Kubeczko@state.co.us>]  
**Sent:** Monday, January 30, 2012 9:04 AM  
**To:** Mitchell, Heather R.  
**Subject:** EnCana Oil & Gas (USA), Albertson G15 7101 Pad, Lot 7 Sec 15 T7S R101W, Garfield County, Form 2A (#400245174) Review

Heather,

I have been reviewing the Albertson G15 7101 Pad **Form 2A** (#400245174). COGCC would like to attach the following conditions of approval (COAs) based on the data EnCana Oil & Gas has submitted on or attached to the Form 2A prior to passing the Oil and Gas Location Assessment (OGLA) review.

1. **General:** The following conditions of approval (COAs) will apply:
  - COA 23** - Operator must ensure 110 percent secondary containment for any volume of fluids contained at well site during drilling and completion operations; including, but not limited to, construction of a berm or diversion dike, diversion/collection trenches within and/or outside of berms/dikes, site grading, or other comparable measures (i.e., best management practices (BMPs) associated with stormwater management) sufficiently protective of nearby surface water. Any berm constructed at the well pad location will be stabilized, inspected at regular intervals (at least every 14 days), and maintained in good condition.
  - COA 5** - Operator must implement best management practices to contain any unintentional release of fluids, including any fluids conveyed via temporary surface pipelines or permanent buried pipelines.

**COA 38** - The moisture content of any drill cuttings in a cuttings pit, trench, or pile shall be as low as practicable to prevent accumulation of liquids greater than de minimis amounts. At the time of closure, the drill cuttings must also meet the applicable standards of table 910-1.

**COA 25** - Flowback and stimulation fluids must be sent to tanks, separators, or other containment/filtering equipment before the fluids can be placed into any pipeline or pit located on the well pad or into tanker trucks for offsite disposal. The flowback and stimulation fluid tanks, separators, or other containment/filtering equipment must be placed on the well pad in an area with additional downgradient perimeter berming. The area where flowback fluids will be stored/reused must be constructed to be sufficiently impervious to contain any spilled or released material.

COGCC would appreciate your concurrence with attaching these COAs to the Form 2A permit prior to passing the OGLA review. If you have any questions, please do not hesitate to call me at (970) 309-2514 (cell), or email. Thanks.

Dave

**David A. Kubeczko, PG**  
**Oil and Gas Location Assessment Specialist**

Colorado Oil & Gas Conservation Commission  
Northwest Area Office  
707 Wapiti Court, Suite 204  
Rifle, CO 81650  
Phone: (970) 625-2497x5  
FAX: (970) 625-5682  
Cell: (970) 309-2514  
[dave.kubeczko@state.co.us](mailto:dave.kubeczko@state.co.us)



 *Please consider the environment before printing this e-mail*

This email communication and any files transmitted with it may contain confidential and or proprietary information and is provided for the use of the intended recipient only. Any review, retransmission or dissemination of this information by anyone other than the intended recipient is prohibited. If you receive this email in error, please contact the sender and delete this communication and any copies immediately. Thank you.

<http://www.encana.com>