



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600257

Date <u>12/31/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>17-12</u>	Lease <u>Morton</u>
County <u>weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>890</u>	
<u>Surface</u>	<u>8 5/8" CSB-24"</u>	Bottom of Surface	Fl. <u>882</u>
Plug	Plug Landed @ <u>838</u>	FL	Time On <u>2115</u>
Production	Pipe Landed @ <u>882</u>	FL	Plug Down <u>0500</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	<u>560</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	<u>186</u>	Miles		
Fuel Surcharge	<u>186</u>	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	<u>0416-</u>	<u>0422</u>
Disp. Rate	5 BPM	Mixing	<u>0422-</u>	<u>0446</u>
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	<u>0446-</u>	<u>0449</u>
Slurry Wt.	14.8 - 15.0 PPG	Displacement	<u>0449-</u>	<u>0500</u>
Water/Cement	6.25 Gal/SK			
Water Temp.	<u>50°F</u>			
Total Slurry Vol.	<u>131.6</u>	BBLS Cement		
Landed Plug @	<u>400</u>	PSI/Final Lift @ <u>200</u>	PSI	
Pre-Flush W/	<u>30</u>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	<u>53.2</u>	BBLS H <sub>2</sub> O	State <u>CO 2.9%</u>	Tax
Circulate	<u>4</u>	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>62</u>			
<u>1214/1217</u>		Bulk Truck		<u>62/62</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Steve, Adam's client

Received By [Signature]  
Customer or His Agent