



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600179

Date 11-8-11	Well Owner Kerr McGee	Well No. 16-1	Lease MORTON
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (XTREME #11)			
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Ft. 881	
Surface	8 5/8" CSG-241	Bottom of Surface	Ft. 876
Plug	Plug Landed @ 831	Ft. Time On 0830	
Production	Pipe Landed @ 876	Ft. Plug Down 1230	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	550	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	186	Miles		
Fuel Surcharge	186	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	1138	1143		
Disp. Rate 5 BPM	1143	1216		
Slurry Vol. 1.32 Cu.Ft./Sk	1216	1219		
Slurry Wt. 14.8 - 15.0 PPG	1219	1230		
Water/Cement 6.25 Gal/SK				
Water Temp. 48°F				
Total Slurry Vol. 129.3	BBLs Cement			
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 20	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 52.8	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		62			
1214/1218		Bulk Truck		162/62			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, EVAN, ERNIE**

Received By

[Signature]
Customer or His Agent