

Well : ARISTOCRAT ANGUS 6-8-3
Field : WATTENBERG
County : WELD State : Colorado
Surface : 1410 FSL, 1274' FEL, NESE Sec. 3-T3N-R65W
:
:
:
Grd Elev : 4778' GR KB Elev : 4791 KB

Well History:

Spud: 10-31-11
TD: 11-05-11

Log Tops:

Sussex 4457'
Niobrara 6984'
Codell 7261'
J Sand 7722'

Surface Casing and Cement

8-5/8", Set @ 630'
Cemented with 245 sxs

Production Casing and Cement

4-1/2" production casing set @ 7879'
Cemented with 600 sxs

Perf'd the Niobrara 6992' - 7047' @ 4 spf
Frac'd the Niobrara 6992' - 7047' (92 holes), w/ 98,658 gals
18 # Vistar hybrid cross linked gel containing 253,980#
20/40 sand. 11-11-11

CFP

Set @ 7120'. 11-11-11

Perf'd the Codell from 7261' - 7278' @ 2 spf
Frac'd the Codell 7261' - 7278', (34 holes) w/ 88,326
gal 22 # Vistar Hybrid cross linked gel containing
251,000 # 20/40 sand. 11-11-11

CFP

Set @ 7330'. 11-11-11

Perf'd the J Sand from 7737' - 7779' @ 2 spf
Frac'd the J-Sand 7737' - 7779', (48 holes) w/ 60,606 gal
18 # Vistar Hybrid cross linked gel containing 250,940#
20/40 Sand. 11-11-11

7892' TD

Drawn by:

Sheilla Reed-High