



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600225

Date <u>11/11/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>9-1</u>	Lease <u>MORTON</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL <u>885</u>	
<input checked="" type="checkbox"/> Surface <u>8 5/8" CSG-24"</u>	Bottom of Surface	FL <u>880</u>	
Plug	Plug Landed @ <u>836</u>	FL	Time On <u>1750</u>
Production	Pipe Landed @ <u>880</u>	Et.	Plug Down <u>0000</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <input checked="" type="checkbox"/> Type III	550	SKS		
Poz-Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack	800/2090			
Mileage Charge	186	Miles		
Fuel Surcharge	186	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	2316-	2322	
Disp. Rate 5 BPM	Mixing	2322-	2346	
Slurry Vol. 1.32 ³ Cu. Ft./Sk	Change Valves	2346-	2349	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	2349-	0000	
Water/Cement 6.25 Gal/SK				
Water Temp. 45°F				
Total Slurry Vol. 129.3	BBLS Cement			
Landed Plug @ 300	PSI/Final Lift @ 100	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 53.1	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 4	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		62			
617/1218		Bulk Truck		62/62			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Kenny Demetrio

Received By Tom Bower
Customer or His Agent