



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600232

Date	11-14-11	Well Owner	Kerr McGee	Well No.	37-1	Lease	MORTON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME II)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	885		
Surface	8 5/8" CSG-244	Bottom of Surface		Ft.	878		
Plug		Plug Landed @	834	Ft.	Time On	2100	
Production		Pipe Landed @	878	Ft.	Plug Down	2315	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	550	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack	2046990 DRI			
Mileage Charge	186	Miles		
Fuel Surcharge	186	MILES		
Additional Cement	40	SKS		
Mixing Rate	4 BPM	Pre-Flush	2221-2226	
Disp. Rate	5 BPM	Mixing	2226-2301	
Slurry Vol.	1.32 Cu. Ft./Sk	Change Valves	2301-2304	
Slurry Wt.	14.8 - 15.0 PPG	Displacement	2304-2315	
Water/Cement	6.25 Gal/SK			
Water Temp.	50°F			
Total Slurry Vol.	138.7	BBLS Cement		
Landed Plug @	800	PSI/Final Lift @ 300	PSI	
Pre-Flush W/	20	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	53.0	BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	4	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		62			
1207/1216		Bulk Truck		62/62			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, CRAIG

Received By Tom Bower  
Customer or His Agent