

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400236879

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Emily Carrender

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6282

3. Address: P O BOX 173779

Fax: (720) 929-7282

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33931-00

6. County: WELD

7. Well Name: RIVERBEND

Well Number: 38-12

8. Location: QtrQtr: NENE Section: 13 Township: 1N Range: 67W Meridian: 6

Footage at surface: Distance: 566 feet Direction: FNL Distance: 487 feet Direction: FEL

As Drilled Latitude: 40.056799 As Drilled Longitude: -104.831497

GPS Data:

Date of Measurement: 12/27/2011 PDOP Reading: 1.8 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 58 feet. Direction: FSL Dist.: 65 feet. Direction: FEL

Sec: 12 Twp: 1N Rng: 67W

** If directional footage at Bottom Hole Dist.: 64 feet. Direction: FSL Dist.: 72 feet. Direction: FEL

Sec: 12 Twp: 1N Rng: 67W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/13/2011 13. Date TD: 11/15/2011 14. Date Casing Set or D&A: 11/16/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8170 TVD** 8075 17 Plug Back Total Depth MD 8141 TVD** 8046

18. Elevations GR 4913 KB 4928

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

PRE FORM 5, LAS CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.0	0	1,014	640	15	1,014	CALC
1ST	7+7/8	4+1/2	11.6	0	8,141	64	7,052	8,160	CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 11/16/2011					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	7,052	976	985	7,052
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,250		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,630		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,219		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,552		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,576		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,005		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Emily Carrender

Title: Operation Specialist I Date: 1/3/2012 Email: emily.carrender@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400236881	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400236882	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400236879	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Engineer	Preliminary Form 5, only LAS version of CBL in document images.	2/22/2012 10:02:08 AM
Permit	Corrected footages for Top of Zone to 58 FSL & 65 FEL, corrected footages for Bottom Hole to 64 FSL & 72 FEL per operator.	2/8/2012 10:28:42 AM
Permit	ON HOLD: Requesting correction to top of zone and bottom hole footages. LAS CBL submitted. changed sec 13 to 12 on top of zone.	2/1/2012 3:31:00 PM

Total: 3 comment(s)