



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600263

Date 12-2-11	Well Owner Kerr McGee	Well No. 23-1	Lease MORTON
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (XTREME #11)			
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Fl.	
(Surface) 8 5/8" CSG-24 #	Bottom of Surface	Fl. 886	
Plug	Plug Landed @ 841	Fl.	Time On 1200
Production	Pipe Landed @ 886	Fl.	Plug Down 1745

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 100% EXCESS	560	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Ceta 1/4 # Per Sack				
Mileage Charge	186	Miles		
Fuel Surcharge	186	MILES		
Additional Cement	40	SKS		
Mixing Rate 4 BPM	1650	1655		
Disp. Rate 5 BPM	1655	1731		
Slurry Vol. 1.32 ³ Cu.Ft./Sk	1731	1734		
Slurry Wt. 14.8 - 15.0 PPG	1734	1745		
Water/Cement 6.25 Gal/SK				
Water Temp. 46 °F				
Total Slurry Vol. 141.0 BBLs Cement				
Landed Plug @ 350 PSI/Final Lift @ 330 PSI				
Pre-Flush W/ 20 BBLs H ₂ O				
Displace W/ 53.4 BBLs H ₂ O				
Circulate 5 BBLs Cement				
Sub Total				
Tax				
Total				

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		62			
1214/1217		Bulk Truck		62/62			

We do not assume any responsibility for any damage or conditions resulting from our services, or pricing, is subject to review and revision.

Delivered By **JOE, JOSH, EVAN, ERNIE**

Received By

[Signature]
Customer or His Agent