



24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached mineral lease description.

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 9046

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	410	169	410	0
1ST	7+7/8	4+1/2	11.6	0	6,791	154	6,791	5,941

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments Conductor casing will not be used on this well. Wellbore Spacing Unit: T5N62W: Sec 19: SENE, NESE; Sec 20: SWNW and NWSW.

34. Location ID: 413543

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Keith Caplan

Title: Sr. Operations Tech Date: 1/30/2012 Email: KCaplan@bonanzacr.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashine Director of COGCC Date: 2/25/2012

<b>API NUMBER</b>
05 123 35128 00

Permit Number: \_\_\_\_\_ Expiration Date: 2/24/2014

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to John Montoya by e-mail at John.Montoya@state.co.us. Indicate Spud Notice in the subject line and provide the following information: Operator Name, Well Name and Number, API #, Spud Date, Contact Name, Contact Phone #, Email Address.
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) If dry hole, set 40 sks cement 50' above Niobrara top, 50 sks cement from 50' below to 50' above surface casing shoe, 15 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.
- 4) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Operator must meet water well sampling requirements as per Rule 318A.

### **Attachment Check List**

Att Doc Num	Name
2063823	SURFACE CASING CHECK
400231375	FORM 2 SUBMITTED
400231617	PLAT
400231619	LEGAL/LEASE DESCRIPTION
400231620	UNIT CONFIGURATION MAP
400245602	DEVIATED DRILLING PLAN
400245603	DIRECTIONAL DATA
400247014	PROPOSED SPACING UNIT
400247116	SURFACE AGRMT/SURETY

Total Attach: 9 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	No LGD or public comment received; final review completed.	2/22/2012 7:41:20 AM
Permit	Operator corrected plugging bond. This form has passed completeness.	1/31/2012 7:41:43 AM
Permit	Returned to draft. Invalid plugging bond.	1/31/2012 7:26:04 AM

Total: 3 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)