

FORM
2Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400230815

PluggingBond SuretyID

20070004

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐Refiling ☐Sidetrack ☐3. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY LLC4. COGCC Operator Number: 89605. Address: P O BOX 21974City: BAKERSFIELD State: CA Zip: 933906. Contact Name: Keith Caplan Phone: (720)440-6100 Fax: (720)279-2331Email: KCaplan@bonanzacrk.com7. Well Name: Antelope Well Number: B-19

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7110

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 19 Twp: 5N Rng: 62W Meridian: 6Latitude: 40.390080 Longitude: -104.367930Footage at Surface: 693 feet FNL/FSL 1977 feet FEL/FWL FWL11. Field Name: Wattenberg Field Number: 9075012. Ground Elevation: 4605 13. County: WELD

14. GPS Data:

Date of Measurement: 11/22/2011 PDOP Reading: 2.8 Instrument Operator's Name: Wyatt Hall15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**Footage at Top of Prod Zone: FNL/FSL 1310 FNL 50 FWL FWL Bottom Hole: FNL/FSL 1310 FNL 50 FWL FWL
Sec: 19 Twp: 5N Rng: 62W Sec: 19 Twp: 5N Rng: 62W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 325 ft18. Distance to nearest property line: 693 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 865 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara-Codell	NB-CD	1-152	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached mineral lease description.

25. Distance to Nearest Mineral Lease Line: 50 ft

26. Total Acres in Lease: 9046

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	13+1/2	8+5/8	24	0	410	241	410	0
1ST	7+7/8	4+1/2	11.6	0	7,077	160	7,110	6,227

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used on this well. Wellbore Spacing Unit: T5N62W: Sec 19 Lot 1 and Lot 2; T5N63W Sec 24 NENE and SENE.

34. Location ID: 418233

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Keith Caplan

Title: Sr. Operations Tech Date: 1/31/2012 Email: KCaplan@bonanzacrk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC Date: 2/25/2012

API NUMBER

05 123 35133 00

Permit Number: _____ Expiration Date: 2/24/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well sampling requirements as per Rule 318A.

- 1) Provide 24 hour notice of MIRU to John Montoya by e-mail at John.Montoya@state.co.us. Indicate Spud Notice in the subject line and provide the following information: Operator Name, Well Name and Number, API #, Spud Date, Contact Name, Contact Phone #, Email Address.
- 2) Provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) If dry hole, set 40 sks cement 50' above Niobrara top, 50 sks cement from 50' below to 50' above surface casing shoe, 15 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.
- 4) Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2063823	SURFACE CASING CHECK
400230815	FORM 2 SUBMITTED
400231435	PLAT
400231436	DEVIATED DRILLING PLAN
400231472	LEGAL/LEASE DESCRIPTION
400246643	UNIT CONFIGURATION MAP
400247122	DIRECTIONAL DATA
400247124	PROPOSED SPACING UNIT
400247125	SURFACE AGRMT/SURETY

Total Attach: 9 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comment received; final review completed.	2/22/2012 8:08:00 AM

Total: 1 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)