

FORM
5A

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400255689

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 66571 4. Contact Name: Joan Proulx
2. Name of Operator: OXY USA WTP LP Phone: (970) 263-3641
3. Address: P O BOX 27757 Fax: (970) 263-3694
City: HOUSTON State: TX Zip: 77227

5. API Number 05-045-12224-00 6. County: GARFIELD
7. Well Name: CASCADE CREEK Well Number: 697-15-30D
8. Location: QtrQtr: SENE Section: 15 Township: 6S Range: 97W Meridian: 6
9. Field Name: GRAND VALLEY Field Code: 31290

Completed Interval

FORMATION: WILLIAMS FORK Status: PRODUCING
Treatment Date: 12/07/2011 Date of First Production this formation: 10/27/2006
Perforations Top: 7413 Bottom: 7762 No. Holes: 60 Hole size: 35/100
Provide a brief summary of the formation treatment: Open Hole: ☐
2 stages of slickwater frac with 4,111 bbls of frac fluid and 151,622 lbs of white sand proppant
This formation is commingled with another formation: ☐ Yes ☒ No
Test Information:
Date: 02/19/2012 Hours: 24 Bbls oil: 0 Mcf Gas: 400 Bbls H2O: 339
Calculated 24 hour rate: Bbls oil: 0 Mcf Gas: 400 Bbls H2O: 339 GOR: 0
Test Method: Flowing Casing PSI: 710 Tubing PSI: 390 Choke Size: 24/64
Gas Disposition: SOLD Gas Type: DRY BTU Gas: 1070 API Gravity Oil: 0
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7656 Tbg setting date: 02/17/2011 Packer Depth:
Reason for Non-Production:
Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt
Bridge Plug Depth: Sacks cement on top:

Comment:

Payadd work was done on the 697-15-30D well. Tubing was pulled, two stages were completed, and tubing was re-landed at 7,656'.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Joan Proulx

Title: Regulatory Analyst Date: Email joan_proulx@oxy.com

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)