



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600141

Date	8/29/11	Well Owner	Kerr McGee	Well No.	8-66-5-3H	Lease	Christner
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Ft. 961				
Surface	9 5/8 CSG #36 12 1/4 Hole	Bottom of Surface	Ft. 955				
Plug		Plug Landed @	910	Ft.	Time On	1230	
Production		Pipe Landed @	955	Ft.	Plug Down	1600	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat Type III Duaine Bell	460	SKS
Poz. Mix User ID ZDSB4		
Calcium Chloride WBS/WO/CC 2056389 Del	2.5	%
Gel % Fio-Cete 1/4 # Per Sack G/L Acct. 80012090		
Mileage Charge	180	Miles
Fuel Surcharge	180	miles
Additional Cement		SKS
Mixing Rate 4 BPM	Pre-Flush 1510	1516
Disp. Rate 5 BPM	Mixing 1516	1543
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves 1543	1546
Slurry Wt. 14.8 - 15.0 PPG	Displacement 1546	1600
Water/Cement 6.25 Gal/SK		
Water Temp. 59 °F		
Total Slurry Vol. 108.1	BBLs Cement	
Landed Plug @ 850	PSI/Final Lift @ 520	PSI
Pre-Flush W/ 20	BBLs H ₂ O	Tax Reference Code
Displace W/ 70.3	BBLs H ₂ O	State CO 2.9%
Circulate 3	BBLs Cement	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		60			
12H/1217		Bulk Truck		60/60			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/Steve/Chris

Received By

Max Harkness

Customer or His Agent