

FORM  
6Rev  
12/05State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Date Received:

08/18/2011

Document Number:

2588077

## WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 10213

Contact Name: DAN MAGEE

Name of Operator: DJ RESOURCES INC

Phone: (303) 595-7439

Address: ONE RIVERWAY STE 1870

Fax: (303) 595-7431

City: HOUSTON State: TX Zip: 77056

Email: DAN@DJRESOURCESINC.COM

For "Intent" 24 hour notice required,

Name: \_\_\_\_\_ Tel: \_\_\_\_\_

COGCC contact:

Email: \_\_\_\_\_

API Number 05-075-09367-00

Well Name: PROPST DJR

Well Number: 2

Location: QtrQtr: NWSW Section: 14 Township: 10N Range: 53W Meridian: 6

County: LOGAN

Federal, Indian or State Lease Number: \_\_\_\_\_

Field Name: BONANZA

Field Number: 7165

☐ Notice of Intent to Abandon☒ Subsequent Report of Abandonment

## Only Complete the Following Background Information for Intent to Abandon

Latitude: 40.840270

Longitude: -103.264490

GPS Data:

Date of Measurement: 07/25/2008

PDOP Reading: 1.6

GPS Instrument Operator's Name: DARREN VEAL

Reason for Abandonment: ☐ Dry ☐ Production for Sub-economic ☐ Mechanical Problems☐ Other \_\_\_\_\_Casing to be pulled: ☐ Yes ☐ No Top of Casing Cement: \_\_\_\_\_Fish in Hole: ☐ Yes ☐ No If yes, explain details belowWellbore has Uncemented Casing leaks: ☐ Yes ☐ No If yes, explain details below

Details: \_\_\_\_\_

## Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
J SAND	4970	4983	01/20/2011		

Total: 1 zone(s)

## Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	11	8+5/8	24	509	215	509	0	
1ST	7+7/8	5+1/2	15.5	4,970	100	4,970	4,100	

## Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #2: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #3: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top. CIBP #4: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.  
CIBP #5: Depth \_\_\_\_\_ with \_\_\_\_\_ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 40 sks cmt from 4983 ft. to 4619 ft. Plug Type: CASING Plug Tagged: ☒

Set 40 sks cmt from 4143 ft. to 4011 ft. Plug Type: CASING Plug Tagged: ☐

Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged: ☐

Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged: ☐

Set \_\_\_\_\_ sks cmt from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Plug Type: \_\_\_\_\_ Plug Tagged: ☐

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

Perforate and squeeze at \_\_\_\_\_ ft. with \_\_\_\_\_ sacks. Leave at least 100 ft. in casing \_\_\_\_\_ CICR Depth

(Cast Iron Cement Retainer Depth)

Set 100 sacks half in. half out surface casing from 565 ft. to 406 ft. Plug Tagged: ☒

Set 18 sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: ☐ Yes ☒ No

Set 0 sacks in rat hole Set 0 sacks in mouse hole

### Additional Plugging Information for Subsequent Report Only

Casing Recovered: 3750 ft. of 5+1/2 inch casing

Plugging Date: 01/20/2011

\*Wireline Contractor: J-W WIRELINE

\*Cementing Contractor: WESTERN WELLSITE SERVICES

Type of Cement and Additives Used: NEAT CEMENT

Flowline/Pipeline has been abandoned per Rule 1103 ☒ Yes ☐ No

\*ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: DAN MAGEE

Title: VP ENGINEERING

Date: 8/31/2011

Email: DAN@DJRESOURCESINC.COM

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: SUTPHIN, DIRK

Date: 2/29/2012

**CONDITIONS OF APPROVAL, IF ANY:**

### **Attachment Check List**

<b>Att Doc Num</b>	<b>Name</b>
2588077	FORM 6 SUBSEQUENT SUBMITTED
2588078	WELLBORE DIAGRAM
2588079	OPERATIONS SUMMARY

Total Attach: 3 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Engineer	Well diagram has top of plug #2 at 4011' not 3750' which is the casing cut depth.	9/15/2011 12:44:16 PM

Total: 1 comment(s)