

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number: 400244094			
PluggingBond SuretyID 20010124			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐
Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP 4. COGCC Operator Number: 47120
5. Address: P O BOX 173779
City: DENVER State: CO Zip: 80217-3779
6. Contact Name: Rebecca Heim Phone: (720)929-6361 Fax: (720)929-7361
Email: rebecca.heim@anadarko.com
7. Well Name: PEHR Well Number: 12-1
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 8436

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 1 Twp: 1N Rng: 67W Meridian: 6
Latitude: 40.076867 Longitude: -104.847843

Footage at Surface: 1498 feet FSL 250 feet FWL

11. Field Name: WATTENBERG Field Number: 90750
12. Ground Elevation: 4944 13. County: WELD

14. GPS Data:

Date of Measurement: 11/23/2010 PDOP Reading: 1.9 Instrument Operator's Name: BEN MILIUS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1980 FSL 660 FWL 1980 FSL 660 FWL
Sec: 1 Twp: 1N Rng: 67W Sec: 1 Twp: 1N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 215 ft

18. Distance to nearest property line: 160 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 940 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
DAKOTA	DKTA	499	320	W/2
J SAND	JSND	232	320	W/2
NIOBRARA CODELL	NB-CD	407	80	W/2SW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____
22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian
23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____
23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached Oil and Gas Lease.

25. Distance to Nearest Mineral Lease Line: 328 ft

26. Total Acres in Lease: 118

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24.0	0	900	630	900	0
1ST	7+7/8	4+1/2	11.6	0	8,436	200	8,436	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used/The surface location of this well is an exception to Rule 318A.a. This well is not within the GWA surface location window due to the number of wells planned for this area and at the request of the surface owner. An exception location request letter and signed waivers are attached to the Form 2 and Form 2A.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Rebecca Heim

Title: Regulatory Analyst II

Date: 2/6/2012

Email: DJRegulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 2/29/2012

API NUMBER

05 123 35189 00

Permit Number: _____

Expiration Date: 2/27/2014

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to COGCC inspector Mike Hickey via e-mail at Mike.Hickey@state.co.us. Indicate Spud Notice in the subject line and provide the following information: Operator Name, Well Name and Number, API #, Spud Date, Contact Name, Contact Phone #, E-mail Address.
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Operator must meet water well testing requirements per Rule 318A.

Attachment Check List

Att Doc Num	Name
1771588	SURFACE CASING CHECK
400244094	FORM 2 SUBMITTED
400244098	DEVIATED DRILLING PLAN
400244099	PLAT
400244100	TOPO MAP
400244101	30 DAY NOTICE LETTER
400244102	OIL & GAS LEASE
400244103	EXCEPTION LOC REQUEST
400244104	EXCEPTION LOC WAIVERS
400244105	OTHER
400248922	DIRECTIONAL DATA

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	2/29/2012 4:08:19 PM
Permit	received confirmation: distance to overhead power lines 215'. changed per operator. Okay to pass pending public comment 2/28/12.	2/14/2012 10:31:01 AM
Permit	ON HOLD: requesting confirmation of distance to public road & overhead powerlines.	2/13/2012 3:54:25 PM
Permit	Operator requests approval of a Rule 318Aa exception location: Wellhead is to be located outside of a GWA drilling window. Request and Waiver attached. No open hole logs will be run.	2/13/2012 3:50:50 PM

Total: 4 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)