

FORM  
5A

Rev  
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400240997

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: Cindy Vue  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832  
3. Address: P O BOX 173779 Fax: (720) 929-7832  
City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33571-00 6. County: WELD  
7. Well Name: GUERRERO Well Number: 35-7  
8. Location: QtrQtr: SWSW Section: 7 Township: 2N Range: 65W Meridian: 6  
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 12/12/2011 Date of First Production this formation: 12/28/2011  
Perforations Top: 7262 Bottom: 7508 No. Holes: 102 Hole size: 0.42

Provide a brief summary of the formation treatment: Open Hole: ☐

NB PERF 7262-7406 HOLES 54 SIZE 0.42 CD PERF 7492-7508 HOLES 48 SIZE 0.38  
Frac Niobrara B & C down 4-1/2" Csg w/ 252 gal 15% HCl & 243,726 gal Slickwater w/ 201,600# 40/70, 4,000# SuperLC  
Frac Codell down 4-1/2" Csg w/ 202,818 gal Slickwater w/ 150,740# 40/70, 4,000# SuperLC

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 01/04/2012 Hours: 24 Bbls oil: 40 Mcf Gas: 292 Bbls H2O: 0  
Calculated 24 hour rate: Bbls oil: 40 Mcf Gas: 292 Bbls H2O: 0 GOR: 7300  
Test Method: FLOWING Casing PSI: 1700 Tubing PSI:          Choke Size: 12/64  
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1327 API Gravity Oil: 52  
Tubing Size:          Tubing Setting Depth:          Tbg setting date:          Packer Depth:         

Reason for Non-Production:

Date formation Abandoned:          Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt         

Bridge Plug Depth:          Sacks cement on top:         

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed:          Print Name: Cindy Vue

Title: Regulatory Analyst II Date: 1/13/2012 Email Cindy.Vue@anadarko.com

### Attachment Check List

Att Doc Num	Name
400240997	FORM 5A SUBMITTED

Total Attach: 1 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
-------------------	----------------	---------------------

--	--	--

Total: 0 comment(s)