



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600253

Date <u>12/30/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>33-18</u>	Lease <u>WARNER</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme "14")</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl.	
<u>Surface</u>	<u>8' 5/8" 1.56-24"</u>	<u>952</u>	
Plug	Bottom of Surface	Fl.	
	<u>946</u>	<u>946</u>	
Production	Plug Landed @ <u>902</u>	Fl.	Time On <u>0500</u>
	Pipe Landed @ <u>946</u>	Fl.	Plug Down <u>0915</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	<u>600</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	<u>132</u>	Miles		
Fuel Surcharge	<u>132</u>	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	<u>0830</u>	<u>0830</u>
Disp. Rate	5 BPM	Mixing	<u>0836</u>	<u>0901</u>
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	<u>0901</u>	<u>0904</u>
Slurry Wt.	14.8 - 15.0 PPG	Displacement	<u>0904</u>	<u>0915</u>
Water/Cement	6.25 Gal/SK		<u>800</u>	<u>12090</u>
Water Temp.	<u>77°F</u>			
Total Slurry Vol.	<u>141</u>	BBLS Cement		
Landed Plug @	<u>500</u>	PSI/Final Lift @ <u>200</u>	PSI	
Pre-Flush Wt.	<u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace Wt.	<u>57.3</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax
Circulate	<u>6</u>	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>			
<u>1217/1218</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Kenny & Demetrio

Received By Danny H.
Customer or His Agent