



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600147

Date	9/28/2011	Well Owner	Kerr McGee	Well No.	32-26H7	Lease	DOUTHIT
County	WAD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP (XTREME #8)						
Address	1999 Broadway, Suite 3700						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl	845		
Surface	95/8 CSG 30"	Bottom of Surface		Fl	835		
Plug		Plug Landed @	791	Fl	Time On	0930	
Production		Pipe Landed @	835	Fl	Plug Down	1600	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat TYPE III	620	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Flo-Cete 1/4 # Per Sack		
Mileage Charge	180	Miles
Fuel Surcharge	180	miles
Additional Cement		SKS
Mixing Rate	4 BPM	Pre-Flush
Disp. Rate	5 BPM	Mixing
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves
Slurry Wt.	14.8 - 15.0 PPG	Displacement
Water/Cement	6.25 Gal/SK	
Water Temp.	68	
Total Slurry Vol.	145.7	BBLS Cement
Landed Plug @	960	PSI/Final Lift @ 400 PSI
Pre-Flush W/	30	BBLS H <sub>2</sub> O
Displace W/	61.1	BBLS H <sub>2</sub> O
Circulate	5	BBLS Cement
		Tax Reference Code
		State CO 2.9%
		Sub Total
		Tax
		Total