



Encana OIL & GAS (USA) INC.

Well location, KM. DH7A-32 C08 799, located as shown in the NE 1/4 NW 1/4 of Section 8, T7S, R99W, 6th P.M., Garfield County, Colorado.

BASIS OF ELEVATION

SPOT ELEVATION AT THE NORTHWEST CORNER OF SECTION 30, T5S, R95W, 6th P.M. TAKEN FROM THE FORKED GULCH QUADRANGLE, COLORADO, GARFIELD COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5966 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

N

1000'

500'

0'

500'

1000'

S C A L E

Sheet 1b of 11

T7S, R99W, 6th P.M.

LEGEND:

= 90° SYMBOL

●

 = PROPOSED WELL HEAD.

▲

 = SECTION CORNERS LOCATED.

△

 = SECTION CORNERS RE-ESTAB.
(Not Set on Ground)

LINE TABLE

LINE	BEARING	LENGTH
L1	S89°46'51"E	129.24'
L2	S89°44'40"E	131.39'

NOTE:

THE PROPERTY LINE IS LOCATED SOUTH 454' FROM THE PROPOSED WELL HEAD.

THE PROPERTY LINE IS LOCATED SOUTH 796' FROM THE PROPOSED LAND PT.

THE PROPERTY LINE IS LOCATED NORTH 652' FROM THE TARGET BOTTOM HOLE..

PDOP = 1.4

NAD 83 (SURFACE LOCATION)

LATITUDE = 39°27'56.55" (39.465708)

LONGITUDE = 108°27'59.84" (108.466622)

NAD 27 (SURFACE LOCATION)

LATITUDE = 39°27'56.63" (39.465731)

LONGITUDE = 108°27'57.52" (108.465978)

NAD 83 (Land Pt)

LATITUDE = 39°27'59.97" (39.466658)

LONGITUDE = 108°28'16.02" (108.471117)

NAD 27 (Land Pt)

LATITUDE = 39°28'00.05" (39.466681)

LONGITUDE = 108°28'13.69" (108.470469)

NAD 83 (Target Bottom Hole)

LATITUDE = 39°29'44.55" (39.495708)

LONGITUDE = 108°28'16.46" (108.471239)

NAD 27 (Target Bottom Hole)

LATITUDE = 39°29'44.63" (39.495731)

LONGITUDE = 108°28'14.13" (108.470592)

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR

REGISTRATION NO. 17492

STATE OF COLORADO

03-06-2012

Revised: 03-07-12 D.R.B.
Revised: 03-05-12 D.R.B.

UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 07-27-10	DATE DRAWN: 02-18-11
PARTY C.R. K.A D.R.B.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE Encana OIL & GAS (USA) INC.	