

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400238048

Date Received:

03/08/2012

PluggingBond SuretyID

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286

Email: jkajiwara@nobleenergyinc.com

7. Well Name: DECHANT H Well Number: 25-65HN

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 11317

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 25 Twp: 3N Rng: 65W Meridian: 6

Latitude: 40.194590 Longitude: -104.619710

Footage at Surface: 2109 feet FNL/FSL FSL 559 feet FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4837 13. County: WELD

14. GPS Data:

Date of Measurement: 10/27/2011 PDOP Reading: 1.9 Instrument Operator's Name: BRIAN T BRINKMAN

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
 2575 FSL 730 FWL 2565 FSL 535 FEL
 Sec: 25 Twp: 3N Rng: 65W Sec: 25 Twp: 3N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3220 ft

18. Distance to nearest property line: 418 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 384 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR	407-87	320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SEE ATTACHED

25. Distance to Nearest Mineral Lease Line: 535 ft

26. Total Acres in Lease: 5709

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	700	348	700	0
1ST	8+3/4	7	26	0	7,294	510	7,294	
1ST LINER	6+1/8	4+1/2	11.6	7100	11,317			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments 2 WELL PAD DECHANT H25-65HN ABD DECGABT G25-64-1HN IS TWINNED WITH KY BLUE H25-12. UNIT CONFIGURATION = N/2S/2, S/2N/2.

34. Location ID: 329123

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JAN KAJIWARA

Title: REGULATORY ANALYST Date: 3/8/2012 Email: jkajiwara@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400238048	FORM 2 SUBMITTED
400259427	30 DAY NOTICE LETTER
400259428	DEVIATED DRILLING PLAN
400259429	WELL LOCATION PLAT
400259431	DIRECTIONAL DATA
400259433	SURFACE AGRMT/SURETY
400259442	LEGAL/LEASE DESCRIPTION
400259443	PROPOSED SPACING UNIT

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Material Handling and Spill Prevention	Spill Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.
Storm Water/Erosion Control	Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.

Total: 3 comment(s)