

Project: Weld County, CO (NAD 83)
 Site: Sec. 25-T3N-R65W (Dechant 25 PAD)
 Well: Dechant H25-65HN
 Design: Plan A - Rev 0 Proposal

Noble Energy

HALLIBURTON
 Sperry Drilling

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/S	+E/W	Dleg	TFace	VSec	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	1500.00	0.00	0.00	1500.00	0.00	0.00	0.00	0.00	0.00	
3	2100.05	15.00	313.29	2093.22	53.56	-56.85	2.50	313.29	-49.73	
4	4065.60	15.00	313.29	3991.78	402.44	427.15	0.00	373.66		
5	4685.65	0.00	0.00	4585.00	456.00	-484.00	2.50	180.00	-423.39	
6	6231.92	0.00	0.00	6151.27	456.00	-484.00	0.00	0.00		
7	7294.42	85.00	89.14	6864.74	165.81	169.70	8.00	89.14	226.44	
8	7389.42	85.00	89.14	6871.28	166.93	244.41	0.00	0.00	300.71	
9	7431.92	90.00	89.14	6874.00	467.87	306.82	8.00	0.00	362.75	
10	11316.55	90.00	89.14	6874.00	526.18	4191.02	0.00	0.00	4223.92	Dechant H25-65HN PlanA - Rev0_BHL_Tgt

True Vertical Depth (400 ft/in)

