



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600279

Date <u>12/11/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>22-1</u>	Lease <u>DECHANT</u>
County	State <u>Colorado</u>		
Charge to	<u>Kerr McGee Oil & Gas Onshore, LP</u>		
Address	<u>1999 Broadway, Suite 3700 (XTREME #14)</u>		
City, State Zip	<u>Denver, Colorado 80202</u>		
Type of Job	Depth	Ft. <u>735</u>	
Surface <u>8 5/8" CSG 24"</u>	Bottom of Surface	Ft. <u>725</u>	
Plug	Plug Landed @ <u>681</u> Ft.	Time On <u>1600</u>	
Production	Pipe Landed @ <u>725</u> Ft.	Plug Down <u>1915</u>	

Description	Qty.	Meas.	Unit Price	Amount
Sat Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>460</u>	SKS		
Poz. Mix <u>MIKE LINGREEN</u>				
Calcium Chloride <u>User ID ZMDL6</u>	2.5	%		
Gel % <u>Fio-Cete 1/4 # Per Sack</u>				
Mileage Charge <u>WBS/WO/CC</u>	<u>132</u>	Miles		
Fuel Surcharge <u>G/L Acct. 80012090</u>	<u>132</u>	MILES		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>1633</u>	<u>1637</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>1637</u>	<u>1904</u>	
Slurry Vol. <u>1.32 Cu. Ft./Sk</u>	Change Valves	<u>1904</u>	<u>1907</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>1907</u>	<u>1915</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp. <u>52</u>				
Total Slurry Vol. <u>108.1</u>	BBLS Cement			
Landed Plug @ <u>275</u>	PSI/Final Lift @ <u>180</u>	PSI		
Pre-Flush W/ <u>20</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>43.3</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>5</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>44</u>			
<u>1214/1214</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/Jason

Received By Codi Sanders
Customer or His Agent